

Leicester Elementary School External Staircase Removal and Replacement Scope of Work

District expectations:

- **Work is to be completed no later than December 30, 2020**

Scope of Work to include:

- **Leicester Elementary School staircase (external) to access lower fields**
 - Demo of the existing stairs and proper disposal of all materials.
 - Approximate current dimensions are 5ft (w) x 50 ft (l)
 - Remove top and bottom pavement aprons and dispose of existing material.
 - Provide and install new concrete upper and lower aprons.
 - Dig footings and pour concrete support columns.
 - Install new stairs with composite decking material.
 - Install new handrails (on both sides) for the length of the entire staircase, with PVC material.

1. Quotes are due by 12:00 pm, Wednesday, December 2, 2020 at 12:00 p.m.
Quotes can be sent to:

Cady Maynard
Director of Finance and Operations
Leicester Public Schools
3 Washburn Square, 3rd Floor
Leicester, MA 01524
-or- via email at: maynardc@lpsma.net

2. Prevailing wage applies; for a prevailing wage sheet on this project, please email maynardc@lpsma.net.
3. Permits and associated fees (as necessary) will be the responsibility of the contractor.
4. A performance bond will be required of the vendor who is awarded the work, in the amount of 50% of the contract price. The District will be flexible on receipt of the bond but expects it within 15 *business days*.
5. A walk-through is to be held on Tuesday, November 24, 2020, at the Leicester Elementary School, 170 Paxton Street, Leicester, MA 01524 at 10:00 a.m.